

**SURVEY &
REMONUMENTATION**

APR 26 1995

COMMISSION

BAY COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Bay _____
(County)

Located In: Corner Code -##

1. Public Land Survey	T	<u>14</u> N.	R	<u>5</u> E.	<u>B-5</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

RECEIVED
 JAN 6 3 54 PM '95
 REGISTERED
 BAY COUNTY REGISTER
 REGISTERED
 REGISTERED

003 163
Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
 2. Private Claims _____

Ronald C. Prevost, in a field survey on October 26, 19 94,
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

3. Description of original monument and accessories and/or subsequent restoration:

B-5 Post Set by John Mullet, 1839
 B. Ash 10 N.77°W. 25 L
 B. Ash 5 N.68°E. 11 L
 LCRC L1 P161, DeLaMater, 1971, Iron.
 LCRC L2 P605, Hughes, 1989, 3/8" Rod in Water Stop Box.
 Recorded Surveys L657 P282, L840 P660.

4. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5 Found 3/8" Rod in Mon. Box, and Recorded Witnesses as follows:
 North 32.15 P. Pole Nail W. Face, L2 P605. (32.23 1994)
 S. 5°E. 50.50 6" R. Pine w/nail, L2 P605. (50.45 1994)
 S. 50°W. 47.60 P. Pole Nail E. Face. (47.54 1994)

Note: Bridge mentioned in LCRC L1 P161 non-existent.

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 27 Oct 94
MM
 Michael MacDonald P.S.
 County Representative

5. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5 Set 5/8" Re-rod and 2 1/2" Bay Co. Brass Cap in Existing Mon. Box 11-10-94 in location of 3/8" rod found.
 Nail W. Face P. Pole North 32.23
 Nail W. Face 12" Pine S.05°E. 50.45
 Nail NW Face P. Pole S.50°W. 47.54
 Face Curb South 29.45



Signed by Ronald C. Prevost
 Surveyor's Michigan License No. 24612

Date 12-30-94