

**SURVEY &
REMONUMENTATION**

APR 26 1995

BAY COUNTY REMONUMENTATION

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Bay

(County)	Located In:	Corner Code #/1
Public Land Survey	T <u>14 N.</u> R <u>5 E.</u>	<u>C-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Lot No. _____, Recorded Plat _____
Private Claims _____

REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN
 APR 26 3 54 PM '95

RECORDED

003 165
Register of Deeds Stamp & File Number

Ronald C. Prevost, in a field survey on October 26, 1994,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Description of original monument and accessories and/or subsequent restoration:

C-1 Post Sct by John Mullet, 1839
 Maple 16 N.37°W. 11 Lks
 B. Ash 10 N.85°E. 22 Lks
 LCRC L2 P495, Prevost, 1978, 1" Iron Pipe.
 LCRC L2 P606, Hughes, 1989, 7/8" Rod.
 LCRC L3 P1, Juras, 1991, 7/8" Rod in Mon. Box.
 Recorded Surveys L695 P87, L713 P566, L772 P200, L832 P4, L836 P605, L1057 P920.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1 Found 3/4" Bar in Mon. Box and Recorded Witnesses as follows:
 S.45°E., 79.35 Cor. Bldg. L2 P495, L2 P606 (79.34 1994)
 N.45°E., 40.41, 40.55, Ctr. Hyd. L2 P495, L3 P1 (40.62 1994)
 N.50°W., 64.05, 64.15 L2 P606, L3 P1 (64.07 1994)
 S.65°W., 59.20, Nail & Tag P. Pole L2 P606 & L3 P1 (59.24 1994)

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 27 Oct 94
MM
 Michael MacDonald P.S.
 County Representative

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 Placed 5/8" Re-rod 2 1/2" Bay Co. Brass Cap in Existing Mon. Box, 11-10-94 in location of 3/4" bar found.
 Center Hyd. N.45°E. 40.62
 SW Cor. Blk. Bldg. N.40°E. 95.42
 SE Cor. Blk. Bldg. N.50°W 64.07
 Nail & Tag in P. Pole S.70°W. 59.24
 NW Cor. Blk. Bldg. S.45°E. 79.34



Signed by Ronald C. Prevost
 Surveyor's Michigan License No. 24612

Date 12-30-94