

# SURVEY & REMONUMENTATION

APR 26 1995

COMMISSION

## BAY COUNTY REMONUMENTATION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
 BAY COUNTY REGISTER  
 JAN 6 3 55 PM '95

RECORDED

or corners in  
Bay  
(County)

Located In: Corner Code //

Public Land Survey	T	14 N	R	5 E	C-6
	T		R		
	T		R		
	T		R		
Property Controlling in Section	S		T	R	
	S		T	R	
Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

003 170

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Ronald C. Prevost in a field survey on October 26, 19 94,  
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

C-6 Post Set by John Mullet, 1839  
W. Oak 30 N.25 E 8 L  
Maple 5 S.74 W 19 L  
LCRC L2 P607, Hughes, 1989, 1" Pipe/Mon. Box.  
M.D.O.T. Witnesses, 1975.  
M.D.O.T. Witnesses, 1994.  
Recorded Surveys L1003 P954, L1035 P504, L1191 P663, L1305 P6.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6 Found 1" Pipe in Mon. Box and Recorded Witnesses as follows:  
N.55° W. 80.90 P. Pole L2 P607, 80.9 M.D.O.T. 1975, 80.83 M.D.O.T. 1994 (80.72 m)  
S.70° W. 75.77 Top Hyd. L2 P607, 75.77 M.D.O.T. 1975, 75.83 M.D.O.T. 1994 (75.80 m)  
S.85° E. 54.95 M.D.O. T. 1994 (54.93 m)  
S.45° E. 68.66 T. Pole M.D.O.T. 1994 (68.19 to set nail in T. pole 1994)

APPROVED LAND CORNER  
P.A. 345 OF 1990 - Bay County  
Date 27 Oct 94  
MM  
Michael MacDonald P.S.  
County Representative

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6 Placed 5/8" Re-rod and Bay Co. 2 1/2" Brass Cap in Existing Mon. Box in place of 1" pipe.  
Nail S. Face P. Pole N.55°W. 80.72  
M.D.O.T. Tag N. Face P. Pole S.85°E. 54.93  
Center Hyd. S.70°W. 75.80  
Set Bay Co. Tag Face T. Pole S.45°E. 68.19



Signed by Ronald C. Prevost

Date 12-30-94

Surveyor's Michigan License No. 24612