

REMONUMENTATION

APR 26 1995

COMMISSION

BAY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Bay

(County)

Located In:

Corner Code //

1. Public Land Survey

T 14 N.R. 5 E.

C-7

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

RECEIVED  
REGISTER OF DEEDS  
BAY COUNTY, MICHIGAN

JAN 6 3 55 PM '95

RECORDED

003 171

Register of Deeds Stamp & File Number

1. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
2. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Ronald C. Prevost, in a field survey on October 26, 1994, to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

- C-7 Post Set by John Mullet, 1839
  - Beech 6 N 38 W 23 L
  - Sugar 6 S 56 E 4 L
  - LCRC L1 P531, Goss, 1973, Mon. Box
  - LCRC L2 P167, Houth, 1974, 3/4" Iron in Mon. Box
  - LCRC L2 P607, Hughes, 1989, 3/4" Pipe in Mon. Box
  - M.D.O.T. Witnesses 1994 3/4" Rod/Mon. Box
  - Recorded Surveys L788 P9, L1035 P504.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-7 Found 3/4" Bar in Mon. Box and Recorded Witnesses as follows:
  - SW 57.0 Face P. Pole L1 P531, 57.47, L2 P167, 57.47, L2 P607, 57.47 M.D.O.T. 1994, (57.45 m)
  - N 35 W 84.80 Top F. Hyd. M.D.O.T., 1994, (84.82 m)

APPROVED LAND CORNER  
P.A. 345 OF 1990 - Bay County  
Date 27 Oct 94  
MM  
Michael MacDonald P.S.  
County Representative

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-7 Placed 5/8" Re-rod, 2 1/2" Bay Co. Brass Cap in Existing Mon. Box in place of 3/4" Bar - 11-10-94.
  - Center Hyd. N35° W. 84.82
  - Center Hyd. N50° E. 72.62
  - Center Hyd. S54° E. 57.10
  - M.D.O.T. Tag SE Face P. Pole S.70°W. - 57.45
  - Set Bay Co. Tag NW Face P. Pole S.60°E. - 57.57



Signed by Ronald C. Prevost

Date 12-30-94

Surveyor's Michigan License No. 24612