

BAY COUNTY REMONUMENTATION 1999

RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

1999 DEC 28 P 1:00

Bay _____ (County)	Located In: Hampton Twp.	Corner Code #
1. Public Land Survey	T <u>14 N</u> R <u>5 E</u>	<u>K-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Barbara Tavel DeWitt
REGISTER OF DEEDS
BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Roger P. Mahoney, in a field survey on 11-13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-4 Post set by Mullet in 1839.
LCRC Ankrom 1986. Found 1" solid iron with crockery and remains of wood stake - set re-rod and cap from old 1932 survey in Section 12.
Found 1/2" re-rod - LCRC Hughes - 1989.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-4 Found 1/2" rod with road cone surrounding.
Accepted the 1/2" rod as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 Replaced 1/2" rebar with 5/8" bar and Bay County remon cap stamped 41105.
West 20.04' - set spike in S. face 4" Ash.
East 117.0' - centerline Weadock Road (Recd 117.0').
S.35E. 9.63' - set spike in W. Face 30" stump.
East 21.0' - set spike in W. face Multiple 4" Willow.
S.40°W. 33.0' - Rotted 24" stump (Recd 33.46' 20" Willow).



Signed by Roger P. Mahoney
Roger P. Mahoney

Date 12-22-99

Surveyor's Michigan License No. 41105

APPROVED LAND CORNER
P.A. 345 OF 1990 - Bay County
Date 10-21-99
MH
Michael MacDonald P.S.
County Representative

004 276