

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Form with fields for Bay (County), Located In: Hampton Twp., Corner Code #, and numbered sections 1-5 for Public Land Survey, Property Controlling, and Miscellaneous Property.

1999 DEC 28 P 1:00

Barbara Tonawalla
REGISTER OF DEEDS
BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Num

4. Lot No. , Recorded Plat
5. Private Claims

I, Roger P. Mahoney, in a field survey on 9-16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-K and rows 1-13, containing numbers 1-35.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-3 Post set by Wampler, 1821. Iron - Consumers Power Company witness sheet - No witnesses given - No date. No further evidence of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3 No corner found. No apparent occupation lines found. Set temporary corner by single proportion and on line between K-3 and M-3. Distance to K-3 2639.24 (2640 GLO) and distance to M-3 2639.24 (2640 GLO). 1958 survey by Consumers Power Company Dwg #S-F-16227 shows West side of survey being on N.& S. 1/4 line. After setting temporary corner, the N.& S. 1/4 line was within 0.10' of West side of the Consumers Power Company survey.

Accepted the temporary corner as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 Replaced temporary corner with 5/8" rod and Bay County remon cap stamped 41105. S.15°E. - 82.50' - spike in S'ly face high tension power pole. S.07°E. - 89.66' - spike in S'ly face high tension power pole. N.12°W. - 32.20' - SE leg transformer tower (at splice). N.41°W. - 55.70' - NW leg transformer tower (at splice).



Signed by Roger P. Mahoney
Roger P. Mahoney

Date 12-22-99

APPROVED LAND CORNER
P.A. 345 OF 1990 - Bay County
Date 12-20-99
Michael MacDonald P.S.
County Representative

Surveyor's Michigan License No. 41105

004 286