

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

1999 DEC 28 P 1:00

For corners in

Form with fields for Bay (County), Located In: Hampton Twp., Corner Code #, and numbered sections 1-3 for Public Land Survey, Property Controlling, and Miscellaneous Property in Sec.

Handwritten signature: Charles Torres... REGISTER OF DEEDS BAY COUNTY, MICHIGAN Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Roger P. Mahoney, in a field survey on 10-25, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13, containing numbers 6 through 36.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-5 Post set by Wampler, 1821. No mon type listed - survey by Williams and Works, 1974. Found - survey by Edmands Engineering, 1977, 1978. Pipe - survey by Edmands Engineering, 1984. Found - survey by Burgin, 1985. Found - survey by Wade-Trim, 1991. Found "T" iron - LCRC by Juras, 1995. Found "T" iron and replaced with concrete mon for NW corner of North Hampton Estates - LCRC by Juras, 1996

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-5 Found conc. monument with cap #33980 as described in LCRC by Juras. Measured 2677.79' to M-5 (rec'd 2677.78').

Accepted the found monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-5 Replace the monument with 5/8" rebar and Bay County remon cap stamped 41105. S.85°W. - 35.86' - nail w/ribbon in S. face 10" Poplar. S.80°E. - 1.27' - center landscape light pole. N.80°W. - 29.90' - nail and Bay County tag in N. face 4" Poplar (rec'd 30.34' to PK nail). S.24°W. - 84.36' - nail and Bay County tag in W. face 8" Poplar.



Signed by Roger P. Mahoney (handwritten signature) Roger P. Mahoney

Date 12-22-99

Surveyor's Michigan License No. 41105

APPROVED LAND CORNER P.A. 345 OF 1990 - Bay County Date 6/22/99 Michael MacDonald P.S. County Representative 004 279