

BAY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970


For corners in Bay
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T	14 N.	R	5 E.	L-11
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

REGISTERED
 DEC 22 12 35 PM '95
 REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN
 003 219
 Register of Deeds Stamp & File-Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____



I, Ronald C. Prevost, in a field survey on November 9, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-11 Post Set by Wampler 1821
 Ash 9" N.8 1/2°E. 34 L
 Elm 7" S.37°E 25 L
 LCRC L2, P311 - 3/8" Iron - McGinnis - 1977, Refers to Spike 8.78'N & 4.47'E.
 C.P. Co. Records call for pile of broken concrete, witnesses gone.
 Recorded Surveys L749 P519, L1334 P839, L1325 P731, L1135 P856, L960 P186, L812 P190, L1215 P274, L1135 P828, L921 P596, L893 P536, L883 P298, L980 P887, refer to 3/8" iron recorded location.
 Recorded Surveys L722 P381, L737 P296, refer to 6" spike location 8.78'± N. & 4.47'± E. of recorded corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 Found 1/4" Rod 3" below Bit., also found 1/2" Rod 8.78'± N. & 4.47'± E.
 Most recorded surveys use the recorded point LCRC L2, P311
 Measurement West 2648.18 (2648.4 R) measurement East 2658.23 (2658.6 R & 2658.32 R)
 Holding with 1/4" Rod recorded LCRC L2, P311
 Monument accepted as the best available evidence of the position of the original corner.

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 9 Nov 95
M.M.
 Michael MacDonald P.S.
 County Representative

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 Replaced 1/4" Rod with 5/8" x 24" Re-Bar with 2 3/4" Bay Co. Brass Cap & Placed Mon. Box on 11-15-95
 Tag in W. Face T. Pole N.30°W. 86.38 (N.30°W., 86.38 tag in T.P. LCRC L2, P311)
 Nail in E. Face P. Pole N.30°E. 90.89
 R.R. Spike in N. Face P. & T. Pole S.45°E. 49.62 (S.40°E. 49.7 U.P. Rec Survey L.1334, P.839)
 Set Bay Co. Tag in E. Face P. & T. Pole S.45°W. 53.77

Signed by Ronald C. Prevost
 Surveyor's Michigan License No. 24612

Date 12-8-95

