

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1999 DEC 28 P 1:00

For corners in

<u>Bay</u> (County)	Located in: Hampton Twp.	Corner Code # M-4
1. Public Land Survey	T <u>14 N.</u> R <u>5 E.</u>	<u>M-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

*Barbara Torres DeHaven*  
REGISTER OF DEEDS  
BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Roger P. Mahoney, in a field survey on 10-11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-4 Post set by Wampler, 1821.  
Found 3/8" iron bar - LCRC by Hughes, 1989.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4 Found 3/8" rod from witnesses listed on LCRC by Hughes.  
Distance to M-5 measures 2629.74' (2640' GLO). and distance to M-3 measures 2644.48' (2640' GLO).

Accepted the 3/8" rod as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 Replaced 3/8" rod with 5/8" rod, Bay County remon cap stamped 41105 and mon box. Corner is ±  
9.0' West of E. of Jones Road.  
S.84°E. - 46.63' - P. pole with nail and washer. (rec'd 46.58').  
S.21°E. - 115.0' - center P. pole. (rec'd 115.44').  
S.82°E. - 79.07' - chisled "+" N. face 5" steel gate post 1.0' above ground.  
S.65°E. - 86.38' - chisled "+" S. face 5" steel gate post 1.0' above ground.  
S.60°E. - 127.17' - set nail and Bay County tag SW. face p. pole.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												



Signed by Roger P. Mahoney  
Roger P. Mahoney

Date 12-22-99

Surveyor's Michigan License No. 41105

APPROVED LAND CORNER  
P.A. 345 OF 1990 - Bay County  
Date 12.20.99  
MM  
Michael MacDonald P.S.  
County Representative

004 280