

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 DEC 28 P 1:00

For corners in

Form with fields for Bay (County), Located In: Hampton Twp., Corner Code #, and numbered sections 1-5 for Public Land Survey, Property Controlling, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number
Barbara Torres
REGISTER OF DEEDS
BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Roger P. Mahoney, in a field survey on 11-13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13, containing numbers 1-36.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-5 Post set by Wampler, 1821. Found 1/2" iron pipe - Consumers Power Co. dwg S-F16227, - Survey by Wade-Trim/Edmands, 1991. Found 1/4" iron rod - survey by William and Works Inc., 1974. Found pipe - survey by Edmands Engineering - 1984. Found 3/8" iron - survey by Burgin, 1986, 1988, 1990 - Wade-Trim/Edmands, 1987, 1990. Found 3/8" iron bar -LCRC by Hughes, 1989. Found - survey by Wade-Trim/Edmands, 1991. Found 3/8" iron rod - LCRC by Juras, 1995.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-5 Found 3/8" rod from witnesses on surveys by Consumers Power Company, Williams and Works Inc., Edmands Engineering, Burgin and Wade-Trim/Edmands and LCRC by Hughes and Juras in centerline of Jones and Arms Roads. Accepted the 3/8" rod as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-5 Replaced 3/8" rod with 5/8" bar, Bay County remon cap stamped 41105 and mon box. S.19°E. - 54.95' - top center hydrant. (rec'd 54.90'). S.57°E. - 44.58' - PK nail N. face p. pole. (Rec'd 44.60' to nail and 44.84' to p. pole). S.57°E. - 44.15' - boat spike in NW. face p. pole. (rec'd 44.15'). N.49°E. - 35.74' - center of M.H. (rec'd 35.77'). S.63°W. - 89.50' - NE. corner block foundation house #1993. (Rec'd 89.50'). N.45°W. - 48.32' - N & T #43066 in SW. face T. pole.



Signed by Roger P. Mahoney
Roger P. Mahoney

Date 12-22-99

Surveyor's Michigan License No. 41105

APPROVED LAND CORNER
P.A. 345 OF 1990 - Bay County
Date 6-24-99
Michael MacDonald P.S.
County Representative

004 281