

BAY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Bay
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey		14 N.	5 E.	M-9	
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED
 DEC 22 12 35 PM '95
 REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN
 003 223

Register of Deeds Stamp & File Number

I, Ronald C. Prevost, in a field survey on June 22, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6			5		4		3		2			1
3													
4	7			8		9		10		11			12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-9 Post by Wampler 1821
 Maple 8" S.16°W. 18 L
 Hickory 8" N.56°E. 19 L
 LCRC Recorded as M-9 - L1 P457 Mon. Box - Goss - 1972
 LCRC Recorded as M-9 - L2 P311 Mon. Box - McGinnis - 1974
 LCRC Recorded as A-9 T.14 N.-R.6 E., L12 P618 - 3/8" Iron Bar in Mon Box - Hughes - 1989
 Old Co. Surveyors Records. N.W. 63' to Fork Apple N.E. 31.7 Conc. Hdwl.
 Recorded Surveys L767 P527, L818 P452, L716 P561, L670 P410, L1225 P385, L1161 P297, L968 P470, L834 P710, L1115 P906, L710 P442, L719 P73, L1348 P854, L893 P514

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9 Found 1/4" Rod in Mon. Box
 Distance West 2701.63 (2701.57 R)(2701. R)
 Distance North 2618.77 (2618.69 R)(2618.69 R)(2617.83 R)
 Distance South 2628.95 (2629.12 R)(2629.1 R)(2629.26 R)
 See agreeing witnesses below.
 Monument accepted as the best available evidence of the position of the original corner.

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 22 June 95
MM
 Michael MacDonald P.S.
 County Representative

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 Replaced 1/4" Rod with 5/8" X 24" Re-Bar with 2 3/4" Bay Co. Brass Cap Placed
 Lift Ring & New Cover on Existing Mon. Box on 7-17-95
 Ctr. Hyd. N.70°W. 58.82 (59.0 LCRC L2 P311)
 Nail & M.S.H.D. Tag E. Face P. & T. Pole N.47°E 58.13 (58.2 LCRC L2 P618)
 Nail & R.L.S. Cap #29240 in W. Face T. Pole N.40°W. 60.29
 Nail & M.S.H.D. Tag in W. Face T. Pole S.45°W. 70.74 (70.8 LCRC L2 P618)



Signed by Ronald C. Prevost
 Surveyor's Michigan License No. 24612

Date 12-8-95