

BAY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Bay
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T	14 N.	5 E.	M-11	
	T	_____	_____	_____	_____
	T	_____	_____	_____	_____
	T	_____	_____	_____	_____
	T	_____	_____	_____	_____
2. Property Controlling in Section	S	_____	_____	_____	_____
	S	_____	_____	_____	_____
3. Miscellaneous	S	_____	_____	_____	_____
Property in Section	S	_____	_____	_____	_____

REGISTERED
 DEC 22 12:55 PM '95
 REGISTER OF DEEDS
 BAY COUNTY MICHIGAN

003 225

Register of Deeds Stamp & File Number.

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Ronald C. Prevost, in a field survey on August 17, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11 Post by Wampler 1821
 Elm 16" S.23 1/2°E. 13 L
 Ash 17" N.80°W. 22 L
 LCRC Recorded as M-11 T.14 N.-R.5 E., L2 P311 - 3/8" Iron - McGinnis - 1974
 LCRC Recorded as A-11 T.14 N.-R.6 E., L2 P618 - 3/8" Iron Bar - Hughes - 1989
 LCRC Recorded as A-11 T.14 N.-R.6 E., L2 P540 - 3/8" Rod - Dunton - 1979
 Recorded Surveys L737 P296, L893 P536, L1308 P222, L1325 P731, L1135 P828, L1215 P274, L722 P381, L1334 P839, L921 P59 L818 P456, L818 P457, L1307 P648

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Found Large P.K. Nail at Bit. Surface
 Distance North 2620.07 (2620.09 R)
 Distance West 2658.23 (2658.32 R)(2658.6 R)
 Distance South 2617.03 (2617.59 R)
 See Agreeable Witnesses Below
 Monument accepted as the best available evidence of the position of the original corner.

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 17 Aug 95
M.M.
 Michael MacDonald P.S.
 County Representative

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 Replaced P.K. Nail with 5/8" X 24" Re-Bar with 2 3/4" Bay Co. Brass Cap & placed Mon. Box. Found 3/8" Rod 3" below P.1 Nail while excavating on 9-7-95.

P.K. Nail E. Face P. & T. Pole	N.40°E.	40.62 (40.62 LCRC L2 P311)
P.K. Nail N.E. Face P. Pole	N.60°W.	79.74 (79.3 LCRC L2 P311)
Ctr. Hyd.	N.60°E.	49.06(49.07 LCRC L2 P311)
W. Edge Stop Sign	S.30°E.	28.81



Signed by Ronald C. Prevost
 24612

Date 12-8-95

Surveyor's Michigan License No. _____