

SURVEY & REMONUMENTATION

APR 23 1998

**BAY COUNTY REMONUMENTATION 1997
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**

<u>Bay</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>3E</u>	<u>K-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____	_____
	S _____ T _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____
	S _____ T _____	_____

REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN
 DEC 9 10 54 AM '97
 RECORDED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Ronald C. Prevost, in a field survey on October, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1 Post set by D.S. Hervey Parke, 1831, closing corner 4l Lks. West Co Surveyors infor 1909.
 LCRC L 1 P271, Goss, 1972 mon box (Witnesses gone)
 Act 132 L784 P143, McGinnis, 1976 fnd.
 Act 132 L784 P144 McGinnis 1976 find. Wit's gone.
 Act 132 L968 P433 Ciosek 1984 mon box fnd.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 Found 5/8" rod in mon box.
 Recovered two wits from L784 P143, that agree and support position.
 Agrees ± with W/T-EDS previous measurement to J-1. (2647.89m)
 (2647.72 & 2648.12 rec).
 Peer group approval
 Monument accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 Place Bay Co. re-mon cap on existing 5/8" rod in existing mon box 11-4-97.
 East 20.00 to re-mon corner K-13, T.16 N.-R.3 E. (20.05 rec).
 N.35°E. 94.45 nail & tag #29240 W side P. pole. (94.2 rec).
 S.50°E. 30.45 W. edge W. leg arrow sign.
 S.55°E. 32.40 W. edge E. leg arrow sign.



Signed by Ronald C. Prevost
 Ronald C. Prevost

Date 11-12-97

Surveyor's Michigan License No. 24612

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 23 Oct 97
MJM
 Michael MacDonald P.S.
 County Representative