

SURVEY & REMONUMENTATION

**BAY COUNTY REMONUMENTATION 1997
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APR 23 1998

For corners in **SECTION**

Bay (County)	Located In:	Corner Code #
1. Public Land Survey	T 15N R 3E	L-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED
Dec 9 10 52 AM '97
Deborah Ann Hartman
REGISTER OF DEEDS
BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Ronald C. Prevost, in a field survey on October, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-1 Corner not set in original Gov't survey, 1831.
 Act 132 L812 P193 McGinnis, 1977 on drwg.
 Act 132 L812 P239 McGinnis, 1977 on drwg.
 Act 132 L827 P65 McGinnis, 1977 mon box.
 Act 132 L840 P610 McGinnis, 1978 mon box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-1 Found 1/2" rod in mon box.
 Recovered 1 wit from L827 P65 & L840 P610, that agrees and supports position SW 101.8 NE cor Gar. R. (M 101.76)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-1 Replaced 1/2" rod with 5/8" re-rod, Bay Co. re-mon cap in existing mon box. 11-4-97.
 East 31.65 to remon corner L-13, T.16 N.-R.3 E.
 S.30°W. 101.76 NE corner brick garage. (101.8 rec).
 N.45°W. 82.20 nail & tag E. side P. pole.
 S.15°E. 144.90 nail & tag W. side P. pole.

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 23 Oct 97
MJM
 Michael MacDonald P.S.
 County Representative



Signed by Ronald C. Prevost
 Ronald C. Prevost
 Surveyor's Michigan License No. 24612

Date 11-12-97

