

APR 23 1998

**BAY COUNTY REMONUMENTATION 1997
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

<u>Bay</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>15N</u> R <u>4E</u>	<u>F-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**REGISTER OF DEEDS
BAY COUNTY, MICHIGAN**
Richard G. ...
Dec 9 10 52 AM '97
RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 5-13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-11 Post set by John Burt 1843.
 Sugar 14 S.29 E. 46 Lks.
 No other.
 LCRC L2 P529, Bongiovanni, 1981, found witnesses of record, set P.K.
 LCRC L26 P636 Hughes, 1989 found P.K. from previous wits.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11 Found P.K. nail 5-13-97.
 Rec'd one witness from LCRC L2 P529 that supports position.
 Rec'd one witness from LCRC L2 P636 that supports position.
 Rec'd one witness from Act 132 L818 P464 that supports position.
 Meas't West 2617.60 agrees with w/t dist's 2617.54 & 2617.65.
 Meas't East 2611.73 agrees with w/t dist's 2611.4 & 2611.18.
 Meas't East 2611.73 agrees with Spicer dist's 2611.72
 Peer Group temp approval 5-29-97. Final approval 6-27-97.
 Monument accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11 Replaced P.K. nail with 5/8" Re-rod Bay Co. bronze re-mon cap/mon box 6-3-97.
 N.80°E. 74.53 ctr hydrant (Rec'd 74.43 L2 P529, L2 P636, L818 P464).
 North 58.38 nail & cap E. face P. pole.
 N.75°W. 139.60 spike N. face P. pole.
 South 48.51 nail & cap E. face P. pole (New pole)



Signed by Ronald C. Prevost
 Ronald C. Prevost

Date 11-10-97

Surveyor's Michigan License No. 24612

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 27 June 97
MJM
 Michael MacDonald P.S.