

SURVEY & REMONUMENTATION

APR 23 1998

**BAY COUNTY REMONUMENTATION 1997
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in SECTION

Bay

(County)

Located In: Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|------------|-------------|
| 1. Public Land Survey | T | <u>15N</u> | R | <u>4 E</u> | <u>H-13</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | R | | |
| | S | | R | | |
| 3. Miscellaneous Property in Sec. | S | | R | | |
| | S | | R | | |

Register of Deeds
 BAY COUNTY, MICHIGAN

Dec 10 3 23 PM '97

RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 5-13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-13 Post set by Joseph Wampler, 1822 running West on S. bndry Sec. 34 Township line. Sugar 16" N.65°W. 12 Lks. W. Oak 40" East 42 Lks. Note: T.15 N.-R.4 E., was subdivided running from North to South and closing on the S. Twp. line. No record of, or evidence of original corner or subsequent restoration of use was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 A point was set on a straight line between G-13 and K-13 and mid-way between G-13 and the point of intersection of the East line of Section 34 projected South to Twp. line. Note: The East line of Section 34 was closed upon a Reserve line North of the Twp. line. Accepted by Peer group.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Replaced point mention in Section B above with 5/8" rerod, Bay County re-mon cap and mon box 10-8-97. N.40°E. 154.53 nail E. side P. pole. N.60°W. 294.05 nail E. side P. pole. West 2633.75 to corner G-13.

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 11 Sept 97
HJM
 Michael MacDonald P.S.
 County Representative



Signed by Ronald C. Prevost
 Ronald C. Prevost

Date 11-10-97

Surveyor's Michigan License No. 24612

APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 11 Sept 97
MJM
 Michael MacDonald P.S.