

**SURVEY & REMONUMENTATION**

APR 23 1998

**BAY COUNTY REMONUMENTATION 1997  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For comers in

Bay (County)	Located In:	Comer Code #
1. Public Land Survey	T 15N R 4E	I-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds  
 BAY COUNTY, MICHIGAN

Dec 9 10 52 AM '97

RECORDED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Ronald C. Prevost, in a field survey on 5-15, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-11 Post set by John Burt, 1843, Elm 40" N.10"W. 13 Lks.  
 LCRC L2 P365 MacDonald, 1976, P.K. nail.  
 LCRC L2 P638 Hughes, 1989, P.K. nail.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 Found P.K. nail & 1/2 rod 6" directly below P.K. 5-15-97.  
 Recovered two witnesses from L2 P365 that support position.  
 Recovered three witnesses from L2 P638 that support position.  
 Measurement West 2576.60 & South 2617.37 agree with w/t 2576.58 & 2617.46.  
 Temporary Peer Group approval 5-29-97. Final approval 6-27-97.  
 Monument accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 Replaced P.K. nail with 5/8" re-rod Bay Co. Bronze re-mon cap & mon box 6-4-97.  
 N.40°E. 46.71 nail & cap SE face P. & T. pole. (46.65 & 46.41 L2 P365 & L2 P638).  
 S.20°W. 41.76 P.K. N. face T. pole (41.60 L2 P638).  
 West 105.75 bridge joint E. edge bridge (105.75 L2 P365 & L2 P638).  
 S.60°W. 35.44 nail in top ctr. end guard post.  
 N.70°W. 38.78 nail in top ctr. end guard post.



Signed by Ronald C. Prevost  
 Ronald C. Prevost

Date 11-10-97

Surveyor's Michigan License No. 24612

APPROVED LAND CORNER  
 P.A. 345 OF 1990 - Bay County  
 Date 27 June 97  
MJM  
 Michael MacDonald P.S.  
 County Representative