

SURVEY & REMONUMENTATION

APR 23 1998

**BAY COUNTY REMONUMENTATION 1997
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION
For corners in

Bay (County)	Located In:	Corner Code #
1. Public Land Survey	T 15N R 4E	J-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**REGISTER OF DEEDS
BAY COUNTY, MICHIGAN**
 Dec 10 3 23 PM '97
 RECORDED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 5-13, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13 John Mullet D.S. 1839.
 Survey of that portion of this boundary lying within the Reserve began at Oak tree cor. to Sections 34 and 35.
 East on S. bndry Section 35.
 38.84 stream 1.40 wide Co. S.
 40.00 Qr. Section post in private Reserve.
 61.00 intersect line of private Reserve.
 No record of, or evidence of original corner or subsequent restoration or use was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 A point was set on a straight line between G-13 and K-13 and at single proportion between G-13, as established by D.S. Joseph Wampler 1822, and K-13.
 Peer group approval

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 Replaced point mentioned in Section B above with 5/8" re-rod, Bay Co. re-mon cap, precast in 36" conc. post, set below plow depth, 10-8-97.
 North 117.27 nail S. side 18" Ash.
 N.30°E. 105.90 nail S side 20" Ash.
 N.45°E. 121.41 nail S. side 18" twin Ash.



APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 11 Sept 97
MM
 Michael MacDonald P.S.
 County Representative

Signed by Ronald C. Prevost
 Ronald C. Prevost

Date 11-10-97

Surveyor's Michigan License No. 24612