

MAY 20 1987

COMMISSION

REMON. COR. H-11, GARFIELD TWP.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

003 298

For corners in  
Bay \_\_\_\_\_  
(County)

- |                                       |                         |       |
|---------------------------------------|-------------------------|-------|
| 1. Public Land Survey                 | T 16N R 3E              | H-11  |
|                                       | T _____ R _____         | _____ |
|                                       | T _____ R _____         | _____ |
|                                       | T _____ R _____         | _____ |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____ | _____ |
|                                       | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____ | _____ |
|                                       | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ |                         |       |
| 5. Private Claims _____               |                         |       |

RECORDED

Dec 19 8 41 AM 1996

Register of Deeds Stamp & File Number

Division of Land Surveying  
 REGISTER OF DEEDS  
 BAY COUNTY, MICHIGAN

I, JERRY JONES, in a field survey on OCT 1, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned on lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- H-11 Corner common to Sections 27 and 34  
 GLO, set post, H. PARKS, 1830'S  
 1909, C. Thornthwaite, found post  
 1972, L. McGinnis, rec survey, L-691, P-611, mon box  
 1973, L. McGinnis, rec survey, L-716, P-549, found mon box  
 1973, L. McGinnis, LCRC, L-1, P-591, mon box  
 1974, L. McGinnis, rec survey, L-735, P-574  
 1977, Edmands Engineering, rec survey, L-815, P-432  
 1980, E. Goss, rec survey, L-897, P-315  
 1982, R. L. Merry, rec survey, L-922, P-714  
 1984, R. L. Merry, rec survey, L-1039, P-881  
 1986, D. Burgin, rec survey, L-1035, P-542, 1/2" iron in mon box  
 1986, D. Burgin, rec survey, L-1035, P-536, 1/2" iron in mon box  
 1988, P. Ciosek, rec survey L-1096, P-630, mon box  
 1989, M. MacDonald, rec survey, L-1115, P-870, found mon box  
 1989, P. Ciosek rec survey, L-1115, P-930, iron in mon box  
 1995, L. McGinnis, rec survey, L-1373, P-493, found mon box

APPROVED LAND CORNER  
 P.A. 345 OF 1990 - Bay County  
 Date 18 Oct 96  
MJM  
 Michael MacDonald P.S.  
 County Representative



WITNESS NOTE: Witnesses from above surveys and LCRC's are available in dossier file; which was presented to peer review committee.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H-11 Corner common to Sections 27 and 34  
 Found re-rod in mon box per surveys by ~~C. Thornthwaite~~, L. McGinnis, Edmands Engineering, E. Goss, R. L. Merry, D. Burgin, P. Ciosek, M. MacDonald and LCRC by L. McGinnis

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-11 Corner common to Sections 27 and 34  
 Found re-rod in mon box per surveys by L. McGinnis, Edmands Engineering, E. Goss, R. L. Merry, D. Burgin, P. Ciosek, M. MacDonald and LCRC by L. McGinnis, replaced re-rod with 5/8" rod and brass cap stamped Bay County Remonumentation PS 19838, and is accepted as the best available evidence of the position of the accepted corner.

South, 49.65', nail and BC disc in power pole (1986 wit.)  
 S 25 Deg E, 48.49', centerline 4" steel pipe gate post (1986 wit.)  
 S 60 Deg E, 150.46', nail and BC disc in power pole (1986 wit.)

N 65 Deg W, 196.45', nail and BC disc in power pole  
 South, 8.0', centerline bit road (1973 wit.)

Signed by Jerry L. Jones Date 11/27/96

Surveyor's Michigan License No. 19838