

**BAY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BAY COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T16N R3E</u>	<u>K-1</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

RECORDED
 Dec 30 3 58 PM '97
 Register of Deeds
 BAY COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Paul M. Ciosek, in a field survey on JULY 24, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- K-1
- POST SET BY J. MULLETT D.S. RESURVEY JUNE 1846, 24 LINKS W OF POST
ASPEN 14" S 9°W 92 LINKS
ASPEN 14" S 8°E 84 LINKS
 - SURVEY, L. 824, P. 4, MCGINNIS, (8/24/77) FOUND 3/8" REROD
SW 62.0' (59.3'M) NAIL IN POWER POLE - NEW POLE
SW 62.6' TO SCS TAG IN POWER POLE - NEW POLE
NW 29.77' (30.00'M) TO CENTERLINE W END 48" RCP
N 5°W 52.45' (53.54'M) SE CORNER RAILROAD TIE FENCE POST
E 15.85' (15.88' M.) TO SE CORNER SECTION 35 FND 3/8" REROD
 - LCRC L. 002, P. 549, LEDY FND 3/8" IRON WHICH AGREES WITH OCCUPATION AND ROAD LINES
SW 62.52' TO S.C.S. BMTAG IN PP
NW 46.11' TO CENTER OF 4" TREE
N 10°W 29.94 TO CENTER OF 48" RCP
E 15.88' TO SW COR SEC. 36, T17N, R3E
 - SURVEY, L. 922, P. 327, LEDY, (5/20/92) FND 3/8" IRON BAR
LCRC, L. 2, P. 549, LEDY, (5/20/82) FND 3/8" REROD
SW 62.52' SCS BM TAG IN POWER POLE - NEW POLE
NW 46.11' TO CENTERLINE 4" TREE - GONE
N 10°W 29.94' (30.00' M) TO CENTERLINE 48" RCP
E 15.88 (15.88' M.) TO SW CORNER SECTION 36, T17N, R3E 3/8" REROD

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND A 3/8" REROD 10" BELOW THE SURFACE OF THE ROAD. DUG DOWN 24" INTO SAND. FOUND NO OTHER OBJECTS IN THE AREA. ACCEPTED THE 3/8" REROD OF RECORD AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


K-1 REPLACED FOUND 3/8" REROD WITH 5/8" X 24" REROD WITH BAY COUNTY REMONUMENTATION CAP WITH 3/16" DRILL HOLE IN MONUMENT BOX.
EAST 15.84' 3/8" REROD SW CORNER SECTION 36, T17N, R3E
N 35°E 39.20' SET CAPPED 3/8" REROD
S 45°E 31.74' SET CAPPED 3/8" REROD
S 40°W 20.08' SET CAPPED 3/8" REROD
N 50°W 17.67' SET CAPPED 3.8" REROD
N 15°W 53.82' SET NAIL/TAG E FACE OF RAILROAD TIE FENCE POST
S 50°W 59.25' SET NAIL/TAG SE FACE UTILITY POLE

Signed by Paul M. Ciosek

Surveyor's Michigan License No. 25835

FIELD BOOK , PAGE 9

004 - 68



Date 12/22/97

APPROVED LAND CORNER
P.A. 345 OF 1990 - Bay County
Date 31 July 97
HJM
Michael MacDonald P.S.
County Representative