

**BAY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

| | | |
|---------------------------------------|--------------------------|---------------|
| <u>BAY COUNTY</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>16N</u> R <u>3E</u> | <u>K-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN
 Dec 30 3 39 PM '97

RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Paul M. Ciosek, in a field survey on JUNE 19, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- K-9
- SET POST J. MULLETT D.S., RESURVEY 1846
HEMLOCK 10" N 85°E 21 LINKS
ELM 12" S 22°W 22 LINKS
 - LCRC, L. 1, P. 477, GOSS, (12/23/72), FND 5/8" ROD
 - LCRC, L. 001, P. 567-568, SCHAFER, (5/4/73), FND 1/2" ROD
 - SURVEY, L. 719, P. 332, SCHAFER, (9/19/73) NO CALL
 - SURVEY, L. 735, P. 560, MCGINNIS, (4/2/74) FND 5/8" BAR
 - SURVEY, L. 735, P. 562, MCGINNIS, (4/2/74) FND 5/8" BAR
 - SURVEY, L. 784, P. 167, MCGINNIS, (4/6/76) FND 5/8" BAR
 - SURVEY, L. 900, P. 669, MACDONALD, (3/2/81) FIELD NOTES FND 5/8" IRON
 - SURVEY, L. 939, P. 495, JONES, (6/7/83) FND 1/2" ROD
 - SURVEY, L. 951, P. 418, MCGINNIS, (10/21/83) FND 5/8" BAR
 - SURVEY, L. 1135, P. 274, BURGIN, (11/20/89) FND 1/2" IRON ROD
 - SURVEY, L. 1325, P. 759, MCGINNIS, (5/5/94) NO CALL

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9
SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND A 5/8" REROD 1" BELOW ASPHALT ROAD SURFACE. AT 1.7' BELOW THE ROAD SURFACE 5/8" REROD GOES INTO 2" PIPE. ACCEPTED THE FOUND 5/8" REROD IN 2" PIPE AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9
DROVE DOWN THE 5/8" REROD IN 2" PIPE WITH A 5/8" X 24" REROD WITH A BAY COUNTY REMONUMENTATION CAP WITH 3/16" DRILL HOLE IN MONUMENT BOX
N 50° E 30.66 SET 3/8" CAPPED IRON
S 48° E 30.18 SET 3/8 CAPPED IRON
S 25° W 39.29 PK/REMON PK & TAG IN W. END 42" CMP
S 42°W 80.47 (80.3 R) REMON TAG NORTHWEST FACE OF POWER POLE
S 51°W 33.11 SET 3/8" CAPPED IRON
N 48° W 26.12 SET 3/8" CAPPED IRON
N 45°W 33.95(34.00' R.) SOUTHEAST FACE STREET SIGN

Signed by Paul M. Ciosek

Date 12/22/97

Surveyor's Michigan License No. 25835

FIELD BOOK , PAGE 5

APPROVED LAND CORNER
P.A. 345 OF 1990 - Bay County
Date 27 June 97
MTM
Michael MacDonald P.S.

