

**BAY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BAY COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T16N R3E</u>	<u>L-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Debra Ann Adams
 REGISTER OF DEEDS
 BAY COUNTY, MICHIGAN

DEC 30 3 39 PM '97

RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Paul M. Ciosek, in a field survey on JULY 24, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-3
1. POST SET BY J. MULLETT D.S. 1846
HEMLOCK 8" N 5°W 36 LINKS
MAPLE 12" S 66°W 10 LINKS
 2. SURVEY, L. 660, P. 323, DELAMATER, (8/6/71) FOUND 5/8" BAR
 3. LCRC, L. 001, P. 273, GOSS, (12/21/72) FND 5/8" BAR
 4. SURVEY, L. 774, P. 260, MCGINNIS, (11/24/75) FOUND 5/8" BAR
 5. SURVEY, L. 921, P. 588, MacDONALD, (1/19/82) FOUND 3/8" IRON
 6. LCRC, L. 4, P. 06, RICHARDSON, (4/17/97) FOUND 1/2" ROD

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3
SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND 3/8" REROD AT ASPHALT ROAD SURFACE. EXCAVATED THE AREA AND FOUND NO OTHER OBJECTS. ACCEPTED THE 3/8" REROD AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3
REPLACED FOUND 3/8" REROD WITH 5/8" X 24" REROD WITH BAY COUNTY REMONUMENTATION CAP WITH 3/16" DRILL HOLE IN MONUMENT BOX.
 N 45°W 12.03' SET CAPPED 3/8" REROD
 N 45°E 13.21' SET CAPPED 3/8" REROD
 S 45°W 28.95' SET CAPPED 3/8" REROD
 S 45°E 30.06' SET CAPPED 3/8" REROD
 N 65°E 41.49' SET N/T NW FACE CUTOFF U.P.
 S 30°E 33.90' CENTERLINE STOP SIGN POST
 NORTH 31.44' SET N/T EAST FACE OF EAST MOST TREE IN CLUMP OF 6" ASH TREES

Signed by Paul M. Ciosek Date 12/22/97

Surveyor's Michigan License No. 25835

FIELDBOOK # _____, PAGE 7



APPROVED LAND CORNER
 P.A. 345 OF 1990 - Bay County
 Date 31 July 97
MJM
 Michael MacDonald P.S.
 County Representative

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 198
 REVISED OCT., 199

004 78