

**BAY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>BAY COUNTY</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T16N R3E	<u>M-6</u>
	T16N R4E	<u>A-6</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Division of State Administration  
 REGISTER OF DEEDS  
 BAY COUNTY, MICHIGAN

Dec 30 3 39 PM '97

RECORDED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Paul M. Ciosek, in a field survey on OCTOBER 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- M-6  
 1. POST SET BY J. WAMPLER D.S. 1822  
 HEMLOCK 20° S 53° E 13 LINKS  
 BIRCH 18° N 30° W 15 LINKS  
 CORNER IS COMMON WITH A-6, T16N, R4E  
 2. SURVEY, L. 803, P. 341, MCGINNIS, (11/18/78) 3/8" IRON  
 3. LCRC, L.12 P. 261, MACDONALD, (3/18/77) 3/8" IRON  
 4. SURVEY, L. 812, P. 209, MCGINNIS, (3/12/77) 3/8" IRON  
 5. SURVEY, UNRECORDED, LEDY #21575, (9/3/91) NO CALL

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-6  
 SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND 3/8" x 18" LONG REROD. VERIFIED LOCATION FROM WITNESSES. EXCAVATED THE AREA AND FOUND NO OTHER OBJECTS IN THE AREA. ACCEPTED 3/8" REROD AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-6 REPLACED FOUND 3/8" REROD WITH 5/8" X 24" REROD AND REMONUMENTATION CAP WITH 3/16" DRILL HOLE IN MON BOX N 45°E 16.54' SET CAPPED 3/8" REROD.  
 N 80°E 20.93' SET MAG NAIL IN SOUTH END OF 12" PLASTIC CULVERT  
 S 45°E 92.40'(92.20' R.) TO NW CORNER HOUSE #1742 FOUNDATION  
 S 05°E 112.01' FOUND N/T 9433 IN N. FACE U. POLE  
 WEST 46.99' FOUND N/T 9433 IN N. FACE U. POLE  
 N 40°W 21.10' SET, CAPPED 3/8" REROD

Signed by Paul M. Ciosek

Date 12/22/97

Surveyor's Michigan License No. 25835

FIELD BOOK , PAGE 15



APPROVED LAND CORNER  
 P.A. 345 OF 1990 - Bay County  
 Date 23 Oct 1997  
MJM  
 Michael MacDonald P.S.  
 County Representative

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 197  
 REVISED JAN., 199  
 REVISED OCT., 199