

MAR 17 1999

BAY COUNTY REMONUMENTATION 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Bay (County)	Located In: Mt. Forest Twp.	Corner Code #
1. Public Land Survey	T <u>17 N</u> R <u>3 E</u>	<u>F-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1998 DEC 28 A 9:09
REGISTER OF DEEDS
BAY COUNTY, MICHIGAN

RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 6-24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- F-11 Post set by John Mullett D.S. 1846.
Beech 10" S.64°W. 14 Lks.
Maple 10" N. 2°E. 26 Lks.
LCRC L2, P457 McGinnis #18999 iron 1972.
Act 132 L1343, P526 McVean, #39088, found P.K. set 3/8" iron 1994.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-11 Found 3/8" re-bar w/cap #39088 @ bit surf.
From L2, P457, North 50.3 face P. pole (50.6 M nail & cap E. face).
From L1343, P526, North 50.62 nail & shiner E. side U. pole. (50.6M).
From L1343, P526, South 39.35 1/2" re-bar (39.35M).
From L1343, P526, S.72°E .64.22 capped 3/8" re-bar in shoulder. (64.20M).
From L1343, P526, N.63°E. 56.02 nail & tag NW side double 4" elm (56.40M ctr stump elm).

Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-11 Replaced 3/8" bar with 5/8" nail, Bay Co re-mon cap, mon box.
N.50°E. 50.60 nail & washer E face P. pole.
N.67°E. 56.40 ctr stump of Elm tree.
S.05°W. 39.35 1/2" re-bar.
S.70°E. 64.20 to capped 3/8" re-bar in road shoulder.
N.70°W.144.08 SE cor. tel. riser.



APPROVED LAND CORNER
P.A. 345 OF 1990 - Bay County
Date 23 July 98
MJM
Michael MacDonald P.S.
County Representative

Signed by Ronald C. Prevost
Ronald C. Prevost

Date 12-18-98

Surveyor's Michigan License No. 24612