

JAN 17 1999

SECTION

BAY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>BAY COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>3E</u>	<u>K-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

BAY COUNTY REGISTER OF DEEDS  
 BAY COUNTY, MICHIGAN  
*Barbara Farnes*

1999 JAN -5 A 9:07

RECORDED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, DALE L. WINIECKE, in a field survey on JULY 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same Town and Range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-6  
 POST SET BY J. MULLETT, D.S. MAY 30 1846  
 12" HEMLOCK, S 79°E 40 LINKS  
 14" WHITE PINE, N 79°W 33 LINKS  
 COUNTY SURVEYOR G. TURNER IN 1908 OLD CORNER BY FORMER COUNTY SURVEYOR.  
 FIELD NOTES, LAPHAM AND ASSOC., INC., NO DATE, FOUND 1/2" IRON



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6  
 SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND A 1/2" IRON 0.2' BELOW ASPHALT ROAD SURFACE. EXCAVATED THE AREA UNDER THE 1/2" IRON AND FOUND ROCKS AT 1' BELOW ASPHALT ROAD SURFACE. AT 1.5' BELOW ROAD SURFACE, FOUND A WOOD HUB AND STOPPED EXCAVATION. FOUND NO OTHER OBJECTS IN THE AREA.  
 THE 1/2" IRON WAS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6  
 REPLACED 1/2" IRON REROD WITH A 5/8" x 24" LONG REROD WITH BAY COUNTY REMONUMENTATION CAP IN MONUMENT BOX.  
 S 40°W 221.45' SET NAIL AND TAG IN NORTH FACE OF POWER POLE  
 S 84°W 144.71' TO SOUTHEAST CORNER OF METAL BARN  
 N 45°W 107.10' TO SOUTHEAST CORNER OF HOUSE  
 N 20°W 97.34' SET NAIL AND TAG IN EAST FACE OF 36" MAPLE  
 N 06°E 229.16 SET NAIL AND TAG IN WEST FACE OF POWER POLE  
 EAST 1.4' TO PHYSICAL CENTERLINE OF NINE MILE ROAD

APPROVED LAND CORNER  
 P.A. 945 OF 1990 - Bay County  
 Date: 24 Sept 98  
MJM  
 Michael MacDonald P.S.  
 County Representative

Signed by Dale Winiecke Date 12/30/98  
 Surveyor's Michigan License No. 41915