

MAR 17 1999

BAY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Form with fields for BAY COUNTY (County), Located In: T 18N R 3E, Corner Code # K-9, and numbered sections 1-5 for Public Land Survey, Property Controlling, and Miscellaneous Property.

Vertical stamp: REGISTER OF DEEDS BAY COUNTY, MICHIGAN

Vertical stamp: 1999 JAN -5 A 9:07

Vertical stamp: RECORDED

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, DALE L. WINIECKE, in a field survey on JULY 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same Town and Range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. A dot is marked at row 9, column K.

A. Description of original monument and accessories and/or subsequent restoration:

K-9
POST SET BY J. MULLETT, D.S. MAY 30, 1846
8" MAPLE N48°W 26 LINKS
8" MAPLE S25°E 26 LINKS
COUNTY SURVEYOR C. THORNTWHAITE IN 1911 FOUND OAK POST SET BY FORMER COUNTY SURVEYOR.
SURVEY NOTES LEDY ENGINEERING (1989), FOUND 1/2" ROD.
CERTIFICATE OF SURVEY, L.1135, P.213, D. BURGIN PS#29240 (1989), FOUND 1/2" IRON



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9
SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND A 1/2" REROD 0.70' BELOW TOP OF ASPHALT ROAD SURFACE. EXCAVATED THE AREA UNDER THE 1/2" REROD AND FOUND NO OTHER OBJECTS IN THE AREA.
CHECKED WITNESSES FROM L.1135, P.213, S50°E TO PK IN U. POLE 85.05' (R&M), N60°E TO YIELD SIGN POST 29.9' (R) TO STOP SIGN POST 27.25' (M)
CHECKED LEDY WITNESSES SOUTHWEST TO PK IN U. POLE 85.06' (R&M), SOUTHWEST TO SIGN POST 39.6' (R&M)
THE 1/2" REBAR WAS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9
REPLACED 1/2" REBAR WITH 5/8" x 24" LONG REROD WITH BAY COUNTY REMONUMENTATION CAP IN MONUMENT BOX.
N45°E 46.96' TO SET NAIL AND TAG IN SOUTHWEST FACE OF CEDAR POST
S50°E 85.06' TO FOUND PK NAIL IN UTILITY POST
SOUTHWEST 39.60' TO CENTERLINE OF STOP SIGN POST
NORTHEAST 27.25' TO CENTERLINE OF STOP SIGN POST

APPROVED LAND CORNER
P.A. 315 OF 1990 - Bay County
Date 12 Nov 98
MTM
Michael MacDonald P.S.
County Representative

Signed by Dale Winiecke

Date 12/30/98

Surveyor's Michigan License No. 41915