

MAR 27 1999

SECTION

BAY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for BAY COUNTY (County), Located In: T 18N R 3E, Corner Code #: K-10, and numbered sections 1-5 for Public Land Survey, Property Controlling, Miscellaneous, Lot No., and Private Claims.

Vertical stamp: REGISTER OF DEEDS BAY COUNTY, MICHIGAN

Vertical stamp: 1999 JAN -5 A 9:07

Vertical stamp: RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DALE L. WINIECKE, in a field survey on JULY 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same Town and Range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of column J and row 10.

A. Description of original monument and accessories and/or subsequent restoration:

K-10
POST SET BY J. MULLETT, D.S. MAY 30, 1846
12" ELM S66°W 23 LINKS
10" MAPLE N47°E 23 LINKS

COUNTY SURVEYOR C. THORNTHWAITE IN 1911 FOUND OLD CORNER SET BY FORMER COUNTY SURVEYOR.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10
SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND NO OBJECTS IN THE AREA.
SET POINT AT THE PRORATED DISTANCE PER THE COUNTY SURVEYOR NOTES ON LINE BETWEEN K-11 AND K-9 T18N, R3E BAY COUNTY POSITION WAS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9
SET 5/8" x 24" LONG REBOD WITH BAY COUNTY REMONUMENTATION CAP IN MONUMENT BOX.
N22°E 254.96' TO SET NAIL AND TAG IN SOUTHEAST FACE OF U. POLE
S20°E 117.44' TO SET NAIL AND TAG IN SOUTHEAST FACE OF U. POLE
S43°W 41.15' TO SET 1/2" REBAR W/ CAP #41915
N64°W 25.77' TO SET 1/2" REBAR W/ CAP #41915
WEST 13.5' +/- TO PHYSICAL CENTERLINE IF NINE MILE ROAD
SOUTH 23.5' +/- TO PHYSICAL CENTERLINE OF FIELD DRIVE TO THE WEST

APPROVED LAND CORNER
P.A. 843 OF 1980 - Bay County
Date 12 Nov 98
HJM
Michael MacDonald P.S.
County Representative



Signed by Dale Winiecke
Surveyor's Michigan License No. 41915

Date 12/30/98