

MAR 27 1999

BAY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>BAY COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>3E</u>	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Barbara Foster
REGISTER OF DEEDS
BAY COUNTY, MICHIGAN

1999 JAN -5 A 9: 08

RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, DALE L. WINIECKE, in a field survey on JULY 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same Town and Range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-9
POST SET BY, J. MULLETT, D.S. MAY 30 1846
9" BLACK ASH, N 55°W 19 LINKS
9" BLACK ASH, S 44°E 29 LINKS

COUNTY SURVEYOR NOTES-SECTION 25, T18N, R3E- SET NEW STAKE ON LINE AND EQUAL DISTANCE- G. TURNER-1910 ±

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9
SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND A 1/2" REROD 0.20' BELOW TOP OF GRAVEL ROAD SURFACE. EXCAVATED THE AREA UNDER THE 1/2" REROD AND FOUND NO OTHER OBJECTS IN THE AREA. THE 1/2" REROD WAS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9
REPLACED 1/2" REROD WITH A 5/8" x 24" LONG REROD WITH BAY COUNTY REMONUMENTATION CAP IN MONUMENT BOX.
N 5°W 36.62' SET NAIL AND TAG IN EAST FACE OF 10'TALL CORNER FENCE POST
S 54°E 81.27' SET NAIL AND TAG IN SOUTH FACE 30" COTTONWOOD
S 71°W 81.19' SET NAIL AND TAG IN NORTH FACE 6" ELM
N 80°W 141.22' CENTERLINE TELEPHONE RISER

APPROVED LAND CORNER
PA. 245 OF 1999 - Bay County
Date 12 Nov 98
MJM
Michael MacDonald P.S.
County Representative

Signed by Dale Winiecke
Surveyor's Michigan License No. 41915

Date 12/30/98

