

DEC 1 1999

BAY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Form with fields for BAY COUNTY (County), Located In, Corner Code #, and numbered sections 1-5 for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Vertical stamp: BAY COUNTY, MICHIGAN REGISTER OF DEEDS

Vertical stamp: 1999 JAN -5 A 9: 09

Vertical stamp: RECORDED

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13 for recording purposes.

I, DALE L. WINECKE, in a field survey on JUNE 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-8 POST SET BY L. CLASON IN 1837 15" CEDAR S35°W 13 LINKS 6" CEDAR N45 1/2°W 14 LINKS COUNTY SURVEYOR, C. THORNTHWAITTE IN 1911 FOUND ONE ORIGINAL WITNESS TREE AND SET A CEDAR POST ON LINE AND EQUAL DISTANCE FROM A-9 AND A-7, T18N, R4E 1996 ARENAC COUNTY REMONUMENTATION LCRC, L. 002, P. 079

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 FOUND 5/8" REBAR WITH ARENAC COUNTY REMONUMENTATION CAP, #22438. STANDARD CORNER COMMON TO SECTION 24, T18N, R3E, AND SECTION 19, T18N, R4E. REMONUMENTATION POINT WAS PREVIOUSLY SET IN 1996 ON LINE AND EQUAL DISTANCE FROM A-9 AND A-7. MONUMENT ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER CORNER APPROVED BY ARENAC COUNTY REMONUMENTATION PEER REVIEW GROUP IN 1996.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 FOUND 5/8" REBAR WITH ARENAC COUNTY REMONUMENTATION CAP #22438 APPROXIMATELY 12" BELOW SURFACE, SURROUNDED WITH ROCKS AND A ROCK LYING ON TOP. EAST 28' ± TO NORTH-SOUTH CROP LINE N30°30'E 59.38' TO FOUND NAIL AND TAG IN WEST FACE OF 12" ELM S05°30'E 323.62' TO FOUND NAIL AND TAG IN WEST FACE OF CORNER FENCE POST S20°30'E 315.55' TO FOUND NAIL AND TAG IN EAST FACE OF 10" ASH 6' ABOVE GROUND N49°E 52.17' TO CENTERLINE OF PLUG IN VERTICAL IRRIGATION PIPE

Signed by Dale Winecke Surveyor's Michigan License No. 41915

Date 12/30/98



APPROVED LAND CORNER P.A. 345 OF 1990 - Bay County Date 6 Aug 98 MJD Michael MacDonald P.S. County Representative

004 230