

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 25 N. R. 13 W.	D-8; D-9; E-8
2. PROPERTY CONTROLLING IN SECTION 20	T. 25 N. R. 13 W.	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. S. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 17, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. - Description of original monument and accessories and/or subsequent restoration:  
C. (continued)

15
Drove 1"x5' pipe & set cedar post w/loc.tag
Old corner Fence Post (Fence S & W)
Due S 28.67
3" Maple S86°E 24.00
8" Poplar S65 E 34.96
6" Poplar S05°E 33.34

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-8 Established center of Sec. 20 at the intersection of N-S & E-W one-quarter lines, per std. B.L.M. instructions. Corner falls 75'± N'ly of small open field (potato patch).
- D-9 Recovered 2½' sq. shadow of Haswell stake (1.5' deep) and added DNR monument. Recovered by doubling over found W 1/16 & SW corner of Sec. 20 which fits within 0.3' for distance and two feet for direction.
- E-8 Reestablished corner equidistant and on line between found section corners to N & S.
- 15 Recovered ¾" pipe (believed to have been set by deceased county surveyor Haswell in 1909, that was removed by others during the course of this survey. Drove 1"x5' pipe in hole where ¾" pipe had been removed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-8	D-9	E-8
Set 1½"x36" pipe & cedar post w/loc. tag	Set DNR mon. & ced. post	Set 1½"x36" pipe
7" B.Cherry S04°E 36.3	8" B.Cherry S15°W 70.45	6" Poplar N74°W 35.0
5" B.Cherry N33°W 64.4	18" Maple S18°E 77.01	6" Ash N21°W 92.8
8" B.Cherry S65 E 58.0	25" Maple S60 E 105.85	5" Poplar N39°E 45.3
		Ctr. N-S gravel county road
		Due W 2'
		Set cedar post w/loc. tag
		Due W 33'


SIGNED BY Carl F. Roser DATE 10-6-75

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ COLFAX TOWNSHIP  
BENZIE COUNTY