

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 25 N. R. 13 E. W.	D-3
2. PROPERTY CONTROLLING IN SECTION 5 _____	T. 25 N. R. 13 E. W.	1
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 19, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

D-3 Fd 5/8" rered as set by RLS H. Bruning in 1971 & used by RLS B. Batzer in 1974 survey of Sec.5. Cor. is in line w/ctr. of gravel rd. to N.

1 Re-Established W 1/8 on N. line S-5, T25N-R13W, equidistant btw. NW & N 1/4 S-5 & on S line T26N-R13W per Pettitt sur. 1900± of S-5, Liber "0", Pg.6. The W 1/8 Cor. on S. line of S-32, T26N-R13W, is N89°36'W, 106.26'. Also fd. 1" pipe, S24°W, 62.8'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p style="text-align: center;">D-3</p> <p>Fd 5/8" Re-rod</p> <p>*16" Maple (triple) N70°E 39.90</p> <p>*8" Maple S35°E 32.13</p> <p>*16" Maple S33°W 34.07</p> <p>Set Ced Post w/loc tag N45°E 47.5</p> <p>Ctr E-W Gr. Rd. N. 3'±</p>	<p style="text-align: center;">1</p> <p>Set 5/8"x36" Re-Rod w/RLS Cap</p> <p>12" Maple S41°W 59.3</p> <p>9" Maple S24°E 49.5</p> <p>Set Ced.Post w/loc Tag S 33'</p> <p>Fn line S(in Trees) West 22'±</p> <p>Ctr. E-W gr. rd. S. 8'±</p>
---	--

\*Old Wits.

SIGNED BY Carl F. Roser 3-31-81 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

Colfax Township  
BENZIE COUNTY