

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>25</u> N. <u>13</u> W. <u>13</u>	H-2,; H-3; I-2: H-1
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S., R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 19, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XX

C. Continued:	I-2		H-1
Set 5/8"x36" Re-Rod w/RLS Cap (buried 0.3)			Set DNR Mon & Ced Post
20" Maple S54°W 128.1			4" W. Birch S85°E 50.7
10" R. Pine S12°E 44.2			4" Maple S45°E 50.5
9" R. Pine N66°E 74.7			3" Pin Cherry S88°W 45.3
Set Ced.Post w/loc tag S 33'			

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- H-2 Established Ctr. of Sec.3 at intersection of 1/4 lines.
 - H-3 Established 1/4 cor. midway & on line between fd sec. cor's 1/2 mile W&E; cor. is 17'± East of old fn line N & in approx ctr. of E-W sand-gravel rd.
 - I-2 Re-established E 1/4 cor. of S-3 on line between the NE&SE cor's of S-3 & at prorated distance to U.S.(GLO Sur). Cor. falls 46'±E of Ctr. of N-S sand rd. & 5'±N of ctr. of sand trail e'ly into Grass Lake Camp ground.
 - H-1 Re-established N 1/4 corner of Sec.3, T25N-R13W, on S. line of T26N-R13W, mid-way between the NE & NW Cor's of Sec.3. The S 1/4 Cor. of Sec.34, T26N-R13W, is N89°28'W 119.58'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	H-2		H-3
Set 5/8"x36" Re-rod w/RLS cap & Ced. Post w/loc tag			Drove 5/8"x34" re-rod w/RLS Cap
9" W.Pine S38°W 19.4			11" Cherry N15°W 55.9
9" W.Pine S01°W 35.6			9" Maple (clump) N40°E 35.9
10" W.Pine S80°E 26.2			14" R. Pine S55°W 43.4
Ctr. R.R. Tracks N89°47'W 222.4'			Set Ced.Post w/loc tag S 33'


SIGNED BY Carl F. Roser DATE 3-31-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)
Colfax Township
BENZIE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____