

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 25 N. R. 13 W.	E-2; G-2; F-3; E-3:
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 18, 19 80, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19 _____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XX

C. Continued;

	F-3		E-3
Fd 3" well pt. & added ced post w/loc.tag			Fd. 2" Pipe
12" Cedar N59°W	13.9		6" Ir.Wood N9°W 49.7
9" Maple (twin) S50°W	22.4'		8" Apple Tree N75°E 113.0
6" Maple (twin) Due E	20.8'		12" Maple S55°W 44.5
			Set Ced.Post w/loc Tag N 33'
			Ctr.Gr.Rd. S. East 10'±
			Ctr.tr.rd. W 1/4 North 10'±
			Trail Rd. E North 4'±

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- E-2 Established W 1/4 Cor of Sec.4 at double across 1/8 cor.& Sec.Cor. to S. for lat. & in old N-S fn. line for Dep. This is close to being in line with the old Ctr.& W 1/4 of Sec.5. See old Pettitt Sur. of S-5, Liber "0", P.24.
 - G-2 Re-established E 1/4 Cor.of Sec.4 on straight line btw.NE&SE Cor's of S-4 & at Pro-rated distance to U.S. (G.L.O.Sur.).
 - F-3 Fd.& accepted 3" well point for S 1/4 Sec.4; fits very reasonable for S.P.
 - E-3 Found 2" pipe as recovered & accepted by R.L.S. H.R. Brunning, Aug 8, 1971 (fits Brunnings 3 wit. trees) for SW Cor. Sec.4.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	E-2		G-2
Set DNR Mon. & Ced. Post			Set DNR Mon w/ Ced. Post
6" Maple S15°W	65.5'		10" Maple S67°E 66.8'
9" Maple S51°E	48.4'		5" Cedar S30°E 52.9'
6" Maple N30°E	33.9'		3" Maple N28°W 46.8'
Fn Cor. N-S-W South	28'±		

SIGNED BY Carl F. Roser 3-31-81

DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY

DATE

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR

DATE

(SEAL)

Colfax Township
BENZIE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____