

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 25 N. R. 13 W.	I-3; I-5; I-4; H-4
2. PROPERTY CONTROLLING IN SECTION.....	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S. R. E. W.	
4. LOT NO. ...., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 19, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XX  
 C. Continued:

- H-4  
 Set 5/8"x36" Re-Rod w/RLS Cap & Ced. post w/loc Tag  
 11" R. Pine S44°W 15.7'  
 14" R. Pine N81°E 48.1'  
 29" Maple S10°E 104.03'

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- I-3 Set Cor. in Fd Remains of Cor. Fn post w/fn remains W & N across River, Cor fits U.S. River Ties N & W reasonable.
  - I-5 Established SE Cor. of Sec.10 prorated to G.L.O. Sur. between found Cor's 1 mile N., 2 1/2 miles S., 1/2 mile W., 2 miles E.
  - I-4 Set E 1/4 Cor. Sec.10 midway and online btw. NE & SE Cor's of Sec.10.
  - H-4 Established Ctr. of Sec. 10 at intersection of 1/4 lines. Cor. falls 2' So. & 4' West of eyeball inter. of Fn's (mostly down) from So. & West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |   |  |
|---|---|--|
| <p style="text-align: center;">I-3</p> <p>Set DNR Mon &amp; Ced. Post</p> <p>16" Maple S70°E 26.2</p> <p>9" Maple S20°E 47.2</p> <p>12" Maple S45°W 71.5</p> <p>*S.Bank Betsie River West 85'±</p> <p>*S.Bank Betsie River North 20'±</p> | <p style="text-align: center;">I-5</p> <p>Set DNR Mon &amp; Ced Post</p> <p>7" Maple S15°W 25.3</p> <p>5" Cherry N56°W 110.0</p> <p>3" Balsam N33°E 102.3</p> | <p style="text-align: center;">I-4</p> <p>Set DNR Mon &amp; Ced Post</p> <p>10" Cherry (Clump) S11°E 64.2</p> <p>5" Cherry S61°W 42.8</p> <p>11" Cherry N87°E 29.4</p> |
|---|---|--|


SIGNED BY Carl F. Roser DATE 3-31-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

Colfax Township  
 BENZIE COUNTY