

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 25 N. R. 13 W.	G-5; G-4; H-5
2. PROPERTY CONTROLLING IN SECTION.....	10, T. 25 N. R. 13 W.	3
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. _____ N. R. _____ E. S. _____ W.	
4. LOT NO. _____, RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 19, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX  
C. Continued: 3 H-5

Drove 5/8"x32" Re-rod w/RLS Cap	Set DNR Mon. & Ced. Post
10" R. Pine S45°E 116.4	16" Maple S40°E 157.0
6" R. Pine N85°E 39.0	14" R. Pine N05°W 15.7
P. Pole N35°W 52.00	12" Cherry S80°W 58.5
Set Ced.Post w/Loc Tag E 27'	
Ctr. N-S gravel Rd. W 6'	

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- G-5 Fd & accepted Iron for SE Cor. Sec.9. Cor. is in approx. Ctr. of gravel rd. looking N & W. W'ly ~~row~~ fn of lane to South is 6'± East.
  - G-4 Fd. & Accepted 1 1/4" pipe for E 1/4 Sec.9. Corner is 18'± South of trail to East & in line with old fence remains & field edge berm to E & W.
  - 3 Established 1/8 Cor. per standard BLM instructions. Corner is in line with old fence berm (fn. down) to east.
  - H-5 Established S 1/4 Cor. of Sec.10 in remains of old Cor. fence post, fn N&W. Distance 1/2 mile West to Fd Cor. is 2610.4' & Distance 1/2 mile East to D.P. corner is 2612.7'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5	G-4
Fd Ir. w/Pyramid Top	Fd 1 1/4 Pipe (buried 0.4)
*12" R. Pine N32°W 67.06	7" R. Pine N38°E 56.20
10" R. Pine S61°W 50.13	*17" Cherry(Twin) N78°E 102.17
* P.Pole S65°E 57.58	* P. Pole S07°W 26.27
Set Ced.Post w/Loc Tag S45°E 47.5	Ctr. N-S Gravel Rd.(Winding) W 20'±
	Set Ced.Post w/Loc Tag E 16.5

\*Old Wits

SIGNED BY Carl F. Roser 3-31-81 DATESURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

Colfax Township  
BENZIE COUNTY