

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 25 N. R. 14 W.	B-5; C-5
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION 7	T. 25 N. R. 14 W.	*663.36'-S of #8
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-5 Re-estab. 1/4 Cor. on line & at proportionate Mea. to U.S. between Sec. Cor's. to E&W. Corner fits U.S. stream & Betsie Rv. ties very reasonable considering U.S. Random ties to rivers & streams, underground nature of streams & probable channel change of Betsie Rv. over the years.
- C-5 Fd. & accepted 5/8"X36" Ir. rod & old post & stk. Fits recovered 660' Cor. & 1/8 Cor. to North and overall pattern of retracement survey in this area.
- \* Drove 5/8"X42" re-rod at SW Corner of NW 1/4-NE 1/4-SW 1/4 of Sec. 7; per std. B.L.M. instructions. West bank of Betsie Rv. is due East, 25'+.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	B-5	C-5	*
Set DNR Mon. & Ced. Post		Fd. 5/8"X36" Iron Rod; Added	Drove 5/8"X42" re-rod w/R.L.S cap
8" Cedar S72°W 18.2'		DNR Mon. & Ced. Post w/Loc. Tag.	& set Ced. Post w/Loc. Tag
7" Cedar S10°E 17.7'		10" Tw. Maple S30°E 26.3	15" Cherry S64°W 65.46
5" Cedar N26°E 15.2'		7" Cherry N88°E 24.3	7" Trp. Cherry N43°W 84.24
6" Cedar N38°W 19.9'		6" Trp. Maple N46°W 35.5	Set 5/8" re-rod w/plastic cap
			& Ced. Post N00-02E 132.00
			Set 5/8" re-rod w/plastic cap
			& Ced. Post S89-00E 16.00

SIGNED BY Carl F. Roser 2-12-79 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

WELDON TOWNSHIP  
BENZIE COUNTY