

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 25 N. R. 14 W.	A-3; A-4; A-5; B-3
2. PROPERTY CONTROLLING IN SECTION	T. _____ S. R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Jan. 10, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~XX~~
 C. continued

B-3
 Set DNR Mon. & Ced. Post
 10" Maple S32°W 28.0'
 4" Cherry in clp. S27°E 28.0'
 12" Maple N36°E 54.6'

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- A-3 Re-estab. Sec. Cor. Comm. to Sec's. 6&7(25-14) and Sec's. 1&12(25-15) equidistant & on line between found 1/4 Cor's., 1/2 mile to N. & S. Cor. falls at E. edge old N-S corduroy R.R. grade. Also in low flooded area from (swampy now) dam, no living trees within 500+ of cor. worth witnessing.
- A-4 Fd. 1/2"X24" re-rod & part of old broken C.I. wood stove door (1887+ on door) & three stones on top of each other; in ctr. of old over-grown rd. grade E.&W.
- A-5 Re-estab. Sec. Cor. Comm. to Sec's. 7&18(25-14) and Sec's. 12&13(25-15) equidistant & on line between 1/4 Cor's. to N&S. Fits avg. line of trail rd. to W.
- B-3 Etab. 1/4 Cor. at Pro-rated distance to U.S. & in line between Sec. Cor's. to E&W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3	A-4	A-5
Set D.N.R. Mon & Ced. Post	Fd. 1/2" re-rod; replaced	Set DNR Mon. w/Ced. Post
17" Stub 8' high S79°W 65.3	w/DNR Mon.	5" Maple N28°W 14.60
Ced. Stp. N28°W 31.4	8' Apple N38°E 10.45	5" Tw. Maple N48°E 33.90
Ced. Stp. S52°E 19.9	9" Cherry N60°W 41.24	8" Maple S46°E 42.65
S. Edge Betsie Rv. Due N 275'+	4" Iron Wood S18°W 24.29	Ctr. Tr. Rd. S. Due W 40'+
	Ctr. N-S tr. rd. Due E 68'+	
	Row of large	
	trees easterly Due S 15'+	


SIGNED BY Carl F. Roser DATE 2-12-79

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ WELDON TOWNSHIP
 BENZIE COUNTY