

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 25 N. 14 W.	B-1
2. PROPERTY CONTROLLING IN SECTION - 6	T. 25 N. 14 W.	1; 2
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 12, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-1** Re-estab. N 1/4 Cor. Sec. 6 on South Line of Sec. 31 (26-14) and at pro-rated distance to G.L.O. plat between the NE & NW Cor's. of Sec. 6.
- 1 Estab. W 1/8 Cor. on N. line of Sec. 6, on South Line S-31 (26-14) & at pro-rated distance to G.L.O. plat between the NW&N 1/4 Cor's. of Sec. 6. The W 1/8 Cor. on S. Line Sec. 31 is S89°36'W, 69.61'.
- 2 Estab. E 1/8 Cor. on N. Line of Sec. 6, on South Line of Sec. 31 (26-14) & at pro-rated distance to G.L.O. plat between the N 1/4 & NE Cor's. of Sec. 6. The E 1/8 Cor. on South Line of Sec. 31 is S89°37'W, 207.93'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1	1	2
Set DNR Mon., buried in E-W dirt Co. Rd.	Set 5/8"X40" re-rod w/RLS Cap & set Ced.Post w/Loc. Tag.	Drove 5/8"X40" Re-rod w/RLS Cap & set Ced.Post w/Loc. Tag.
9" R.Pine N14°E 46.46'	4" R.Pine S67°E 107.3	16" Maple N58°W 98.4'
7" R.Pine N41°E 51.13'	4" R.Pine S40°W 82.0	22" Maple N69°E 78.0'
13" Cherry S40°E 93.22'	Ctr. E-W Rd. Due S 16'+	Ctr. E-W Rd. Due N 12'+
Ctr. E-W rd. Due S 9'+		
Set Ced.Post w/Loc. Tag Due S. 25'		
S 1/4 Cor. S-31 (26-14) S89°37'W 139.16		

SIGNED BY Carl F. Roser

DATE 2-12-79

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

WELDON TOWNSHIP
BENZIE COUNTY