

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 25 N. 14 E. R. W.	D-2; D-3
2. PROPERTY CONTROLLING IN SECTION 5	T. 25 N. 14 E. R. W.	8
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 15, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

D-2 Fd. 1 1/2" pipe for ctr. of Sec. 5, per C.P. Tuller Survey of Sec. 5, dated May 1900. Cor. also fits NW Cor. of "Orchardville No. 1".

D-3 Restored 1/4 Cor. from average of plat irons to South; Corner common to "Plat of Orchardville", "Plat of Orchardville No. 2", "Plat of Orchardville No. 3" and "Assessors Plat of Cherry Grove".

8 Established 1/8 Cor equidistant & on line between Ctr. of Sec. & W 1/4 Cor., Sec. 5. Found Iron (buried) is N86°35'W, 4.7'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-2	D-3	8
Fd. 1 1/2" pipe & set	Set DNR Mon. (buried 0.5)	Set 5/8"X40" re-rod w/RLS cap
Cedar Post w/Loc. Tag.	11" Maple S43°W 72.0	& Ced. Post w/Loc. Tag.
9" Cherry (cluster) S36°E 151.7	13" Cherry S70°W 51.3	8" Cherry N60°E 22.7
18" Cherry (cluster) N57°E 110.4	7" Trp. Maple N72°E 58.1	7" Tw. Maple N78°W 18.4
Ctr. narrow N-S dirt rd.	Ced. Post w/Loc. Tag	10" Maple S19°E 20.5
Due E. 16'+	Due S 16.5	
	Ctr E-W Sand Trail	
	Due N 12'+	
	Ctr. N-S Sand Trail	
	Due E 15'+	

SIGNED BY Carl F. Roser DATE 2-12-79


SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____



WELDON TOWNSHIP
BENZIE COUNTY