

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>5</u> , T. <u>25</u>	N. <u>14</u> , R. <u>14</u> E. W.	<u>2; 7; 10</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____	N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 10, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 2 Fd. 1" Sq. Iron Bar (buried 0.5'); adj. 1.38'-W & 2.28'-S to comp. position for 1/8 Cor.

7 Drove 5/8" Re-rod, buried 0.5' in E. Wheel Track of N-S trail road, at found stake bottom shadow per C.P.Tuller Wit., 8" maple, S86°30'E, 10'. Fd. Tuller's maple, now a 36" maple clump, per his notes, record of survey's, Vol. I, Pgs. 6&7, dated May 1900. Cor. fn. remains (all down), fn's. N&E, are 1-rod E. of restored cor. Ctr. of N-S dirt trail road is 3'+ West.

10 Estab. 1/8 Cor. equidistant & on line between 1/4 Cor. North and Sec. Cor. South. Found 3/4" pipe, S00°50'W, 4.11'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	2	7	10
Fd. 1" Sq. Ir. Bar (buried 0.5')		Drove 5/8"X40" re-rod w/RLS Cap	Set 5/8"X40" Re-rod w/RLS Cap & Ced.Post w/Loc.Tag
6" R.Pine N09°W 36.76		36" Map.Clump S86°E 9.8'	5" R.Pine N46°W 52.7'
9" Cherry S43°W 22.95		Approx. SE Cor. Dump-Ced.Post Fn.	17" Maple S40°W 31.7
13" Cherry S68°W 53.11		Cor;(W-W fn. N&W) N78°W 15.3'	12" Maple N61°E 59.9
Set Cedar Post w/Loc. Tag		8" Maple N52°E 58.15'	Ctr. N-S trail rd.
Due S. 26'		Large Maple Clp. Due E 9.8'	Due E 11'+
Ctr. E-W gravel rd.		Set Ced. Post w/Loc. Tag	
Due N. 7'+		Due W 16.5'	
		9" Tw. Maple S62°E 59.27'	

SIGNED BY Carl F. Roser 2-12-79 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

WELDON TOWNSHIP
BENZIE COUNTY

