

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 25 N. 14 W.	E-1
2. PROPERTY CONTROLLING IN SECTION 5 ,T. 25 N. 14 W.		1
3. MISCELLANEOUS PROPERTY IN SECTION ,T. N. S., R. E. W.		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 10, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 E-1 Fd. 3/4"X1 1/4" Ir.; adj. southerly 1.0' to be on line between the SW Cor. & S 1/4 Cor. of Sec. 33, T26N-R14W; replaced adj. fd. Ir. with DNR Mon. The ctr. of E-W gravel road is North, 4'+. The ctr. of crooked trail southerly is West, 17'+. The corner fits C.P. Tuller's survey of Sec. 5 dated May 1900; large brown record of survey's, Vol. I, pgs. 6 & 7. Reg. of Deeds Office.

1 Established W 1/8 Cor. on North Line Sec.5, equidistant & on line between NW & N 1/4 of Sec. 5. Position seems to fit NW Cor. of "Assessor's Subdivision"; no evidence of plat monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1	1	
Set DNR Mont.		
14" Tw. Cherry S44°E 80.7'		Drove 5/8"X40" Re-rod w/RLS Cap(Buried)
13" Tw. Cherry S20°E 112.1'		10" Cherry N07°W 27.4
N.E Cor of Dump		8" Maple S28°W 38.9
Ced. Fn. Post S47°W 46.8		7" Maple S32°E 42.2
Set Ced. Post w/Loc.Tag		Ctr E-W Rd Due N 1'+
Due S 33'+		Set Ced.Post w/Loc. Tag.
		Due So. 33'
Sec. Cor. Comm. to S-32 & 33 (26-14) N89°43'W 296.39'		

SIGNED BY Carl F. Roser 2-12-79 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ WELDON TOWNSHIP
BENZIE COUNTY