

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

SECTION

For Corners In: BENZIE Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 25N R 14W C-11  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

STATE OF MICHIGAN  
BENZIE COUNTY  
RECORDED

1 FEB 2000 1:52:13 PM  
MICHELLE R. GRAY  
REGISTER OF DEEDS  
# PAGES ONE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John B. Smendzuik in a field survey on November 23, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838: GLO set post and witnesses - 24 Sugar S21°E 27 links and 6" Sugar N15°W 9 links. 1911: Frank S. Haswell, Survey Records II, Page 114, says he planted a 1" Iron pipe, 4' long from the original witnesses and old stake. 1988: Unrecorded Certificate of Survey by Max Harris shows he found a 1" iron pipe at this position.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

1999: Found 1" X 35" iron pipe in Intersection of Long Street and Joyfield Road. This iron pipe fits very well with the distances to other Haswell corners to the West and to the South. The Benzie County Peer Group accepted the iron pipe as the best evidence of the perpetuation of the original GLO corner.


Ratified by Peer Group  
In accordance with P.A. 345  
Chairman [Signature]  
Date 11/2/99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed the 1" iron pipe and set a standard 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap, 5" below the grade of the existing gravel road intersection.

- 16" Red Pine S80°E 26.88' to a found nail and set new nail and BCRP tag.
- 11" W. Pine S37°E 38.64' to a found nail and set new nail and BCRP tag.
- Power Pole N42°W 48.00' set nail and BCRP tag.
- Guy Pole N36°E 44.84' set nail and BCRP tag.

Corner is 3' East of the centerline of Long Street and 6' South of the centerline of Joyfield Road.



Signed by: [Signature]  
Surveyor's Michigan License No.: 30895

Date: 1/31/2000