

SECTION

MAR 28 1999

WELDON TOWNSHIP  
For corners in

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
BENZIE COUNTY  
RECORDED

BENZIE COUNTY  
(County)

Located In:	Corner Code #
T 25NR 14W	G-8
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

22 JAN 1999 3:02:23 PM  
MICHELLE R. GRAY  
REGISTER OF DEEDS  
# PAGES ONE

Register of Deeds Stamp & File Number

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

John B. Smendzuik, in a field survey on 12/3, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21	●	22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-8: 1838: GLO set post - Sugar 14" N77°W 14 links and Sugar 10" S65°E 13 links. 1967: BCRC notes show corner established and no evidence how.

Ratified by Peer Group  
In accordance with P.A. 345  
Chairman John B. Smendzuik  
Date 11/24/98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8: 1998: Found 3/4" x 12" iron pipe, 6" below existing grade and on old occupation to West. Iron is 36' South of fence line to East. Iron is on line between corners at G-7 and G-9 and is within 0.87' of a split of the distance between those corners. The Benzie County Peer Group accepted the 3/4" iron pipe as best evidence of an locally accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8: Removed the 3/4" iron pipe and set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap in a monument box.

- 5" Red Pine N33°E 90.44' to found 60D spike in tree with blaze.
- 12" Red Pine N42°W 71.26' to found 60D spike in tree with blaze.
- Power Pole S79°E 32.53' to found 60D spike.
- 16" Maple N33°E 123.73' to found 60D spike.
- Monument box is in the centerline of Pioneer Road.

Signed by John B. Smendzuik  
Surveyor's Michigan License No. 30895

Date 1/22/99