

SECTION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
BENZIE COUNTY  
RECORDED

WELDON TOWNSHIP  
For corners in

BENZIE COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>25NR14W</u>	<u>G-10</u>
	T <u>  </u> R <u>  </u>	<u>  </u>
	T <u>  </u> R <u>  </u>	<u>  </u>
	T <u>  </u> R <u>  </u>	<u>  </u>
2. Property Controlling in Section	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>
	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>
3. Miscellaneous Property in Sec.	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>
	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>

22 JAN 1999 3:02:35 PM  
MICHELLE R. GRAY  
REGISTER OF DEEDS  
# PAGES ONE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John B. Smendzuik, in a field survey on 12/14, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28	●	27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-10: 1838: GLO set post - Beech 8" S63°E 20 links and Beech 8" N58°W 42 links. Undated: Frank Haswell, Surveyor's Record II, Paeg 118, drove 1" x 4" iron pipe from original witness and old stake. 1990: Richard Wilcox found iron pipe at corner and witnessed it. 1997: Bruce Jenema, in an unrecorded Certificate of Survey, shows he found a 1" iron pipe and witnessed it.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10: 1998: Found 1" x 51" iron pipe per Haswell by end fence post remains with barbed wire. The Benzie County Peer Group accepted the 1" iron pipe as best evidence of the perpetuation of the original GLO corner.

Ratified by Peer Group  
In accordance with P.A. 345  
Chairman [Signature]  
Date 11/24/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10: Removed the 1" iron pipe and set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap.

- 20" Maple stump N72°E 3.16' to found 60D spike.
- 10" Red Pine S55°W 37.31' to found 60D spike.
- 10" Maple S63°E 26.98' to found 60D spike.
- 14" Maple S04°E 37.31' to found 60D spike.

Signed by [Signature]  
Surveyor's Michigan License No. 30845

Date 1/22/99