

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

WELDON TOWNSHIP  
For corners in

BENZIE COUNTY  
(County)

Located In: Corner Code #

- 1. Public Land Survey T25N R14W I-8
- T\_\_\_ R\_\_\_
- T\_\_\_ R\_\_\_
- T\_\_\_ R\_\_\_
- 2. Property Controlling S\_\_\_ T\_\_\_ R\_\_\_
- in Section S\_\_\_ T\_\_\_ R\_\_\_
- 3. Miscellaneous S\_\_\_ T\_\_\_ R\_\_\_
- Property in Sec. S\_\_\_ T\_\_\_ R\_\_\_

STATE OF MICHIGAN  
BENZIE COUNTY  
RECORDED

22 JAN 1999 3:03:08 PM  
MICHELLE R. GRAY  
REGISTER OF DEEDS  
# PAGES ONE

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, John B. Smendzuik, in a field survey on 12/14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22	●	23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-8: 1838: GLO set post - Sugar 12" S84°E 34 links and Beech 12" N88°W 47 links. 1995: Phil Case in a LCRC, recorded in Liber 1, Page 315, shows he found a 1" flared iron pipe. He says that the iron pipe fits well to the S.P. position between adjacent section corners.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-8: 1998: Found 1 1/4" x 39" iron pipe on west edge of Weldon Road and fits well with Case witnesses. The Benzie County Peer Group accepted the 1 1/4" iron pipe as best evidence of an locally accepted corner.

Ratified by Peer Group  
In accordance with P.A. 345  
Chairman J. B. Smendzuik  
Date 11/24/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8: Removed the 1 1/4" iron pipe and set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap.

- 6" Maple West 39.06' to found nail in blazed tree.
- 9" Cherry N52°E 55.08' to found nail in blazed tree.
- 14" Aspen S74°E 31.82' to set nail and BCRP tag over found nail in blazed tree.
- 6" Maple S43°E 28.29' to found nail in blazed tree.
- Monument is 8' West of the centerline of Weldon Road, an existing 2 track.

Signed by J. B. Smendzuik Date 1/22/99  
Surveyor's Michigan License No. 30895