

APR 07 1998

LIBER 2 PAGE 112

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
BENZIE COUNTY
RECORDED

19 Jan 1998 9:32:44 AM
MICHELLE R. GRAY
REGISTER OF DEEDS
PAGES ONE

Register of Deeds Stamp & File Number

For corners in

Benzie
(County)

Located In:

Corner Code I-11

- 1. Public Land Survey T 25N R 14W I-11
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling in Section S ___ T ___ R ___
S ___ T ___ R ___
- 3. Miscellaneous Property in Sec. S ___ T ___ R ___
S ___ T ___ R ___
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | ● | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, John B. Smendzuik, in a field survey on December 15, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-11: 1838: GLO set post - Sugar 12" N14°W 24 links and Beech 17" S35°E 6 links. 1898: James A. Pettit, Surveyor's Record No. 1, Page 202, shows distance to corner but no mention of what's there. 1904: E. P. Waterman notes show iron pipe but no witnesses. 1967: BCRC found 1" iron pipe. 1971: BCRC raised to surface with 14" of 1 1/2" pipe. 1972: BCRC placed Benzie County cast iron Harrison Marker over old iron.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


I-11: 1997: Found 13 1/2" of Benzie County cast iron Harrison marker over a 3/4" x 3.5 plus feet of iron pipe. Pipe believed to be set by Pettit as he has used this type of material before at this point in time. The Benzie County Peer Group accepted the Benzie County cast iron Harrison marker as the best evidence of the perpetuation of the GLO corner.

Ratified by Peer Group
In accordance with P.A. 345
Chairman [Signature]
Date 12/10/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11: Removed Benzie County cast iron Harrison marker and left the 3/4" iron pipe in place, it would not come out so we drove it down and over and set a 3" diameter Benzie County Remonumentation Program concrete monument with a brass cap iron monument box.

- 23" Cherry S88°W 51.75' to a found 60D spike.
- USGS Elevation Concrete Monument N87°W 28.81'.
- 13" Red Pine N83°E 54.83' to found double headed nail. (BCRC witness)
- 12" Red Pine N41°E 64.07' to found double headed nail.
- Monument box is in the centerline of Pioneer Road (Co. Road 677).



Signed by [Signature]
Surveyor's Michigan License No. 30895

Date 1/18/98