

SURVEY & REMONUMENTATION

MAY - 1 1995

LIBER 2 PAGE 19

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Benzie</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>25N</u> R <u>14W</u>	<u>M-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 BENZIE COUNTY
 RECORDED

29 DEC 94 4:40 P.M.

MICHELLE R. GRAY
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, John B. Smendzuik, in a field survey on December 16 and 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:

M-7: G.L.O. set post - 14" Sugar N61°W 35.64', 12" Lynn S63°W 17.16'. 1907 - Frank Haswell, Surveyor's Record II, Page 66, set cedar post 2' long, from 1 witness tree. 1982 - Harold Bruning filed Act 74 - corner reset single proportionate measurement to Frank Haswell's distances between 1/4 corners to north and south and set a Benzie County Harrison marker.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7: Found Benzie County Harrison marker pulled and leaning against a tree. Reset from Harold R. Bruning witnesses which were all still in place. The Basswood Tree had broken over but witness nail was still in place.

Ratified by Peer Group
 In accordance with P.A. 345
 Chairman John B. Smendzuik
 Date 12/21/94



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 4-7: Set 3" Ø concrete monument with Benzie County Remonumentation Program Brass Cap from Harold R. Bruning (HRB) witnesses.
- 6" Hard Maple N81°E 23.75' (HRB)
- 8" Basswood N21°E 11.40' (HRB)
- 6" Ash S65°W 2.30' (HRB)
- 4" Hard Maple S34°E 28.90' (HRB)
- Triple 12" Ash S14°W 44.17'

Note: All witnesses marked (HRB) have measurements taken to double headed nail with white tag. The triple 12" Ash has a brass tag stamped B.C.R.P.

Signed by John B. Smendzuik Date 12/29/94
 Surveyor's Michigan License No. 30895