

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Benzie</u> (County)	Located In	Corner Code #
1. Public Land Survey	T <u>25N</u> R <u>14W</u>	<u>J10</u>
	T _____ R _____	_____
2. Property Controlling in Section	S <u>26</u> T <u>25N</u> R <u>14W</u>	<u>9</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on January 8, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		●	●	25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J10 - None

9 - None



B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

J10 - C¹/₄, Sec. 26 - Set 2" Aluminum Cap (Stamped) on 5/8" x 34" Rebar at intersection of 1/4 Line per Standard BLM procedure. Edge of Swamp is 80' ± 20' North.

9 - CE 1/16 Cor., Sec. 26 - Set 2" Aluminum Cap (stamped) on 5/8" x 34" Rebar per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J10 - 2" AC on 5/8" x 34" Rebar
 SW 1' to Set Blue Carsonite Post with location tag.
 S84°W 28.98' to set N&T in N side 10" Hemlock
 N13°E 30.60' to set N&T in E side 5" Beech scribed 'XBT'
 N61°E 42.89' to set N&T in N side 4" Beech scribed 'XBT'
 S4°E 42.53' to set N&T in W side 14" Hemlock

9 - 2" AC on 5/8" x 34" Rebar
 SE 1' to set Blue Carsonite Post with location tag
 N20°E 13.31' to set N&T in NW side 11" Tamerack
 N73°E 28.27' to set N&T in NW side 12" Tamerack
 S57°E 12.07' to set N&T in NE side 8" R. Maple
 S12°W 6.05' to set N&T in W side 6" R. Maple

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 1/27/2003