

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>25</u> ^{N.} _● , R. <u>15</u> ^{W.} _●	K-1; K-3; I-1; I-3
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____, S., R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, S., R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 17, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monuments and accessories and/or subsequent restorations~~

C. (continued)

I-3

1/2" rod in monument box
 on center b'top Co. road E & W
 Center US-31 Due W 3.4
 Tel. Pole N45°W 50.80
 Tel. Pole S73°E 110.35

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-1 Found "T" iron 10 feet E of ctr. of N-S b'top Co. road per previous surveys of record by Consumers Power Co. and R.L.S. H. Bruning.
- K-3 Found Benzie Co. monument in mon. box per previous surveys of record by R.L.S. Bruning.
- I-1 Found 3/8" pipe with plast. cap per previous surveys by R.L.S. H. Bruning & W. Fraser.
- I-3 Found iron in monument box as previously used by M.D.S.H. & R.L.S. H. Bruning.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1	K-3	I-1
Found "T" iron	Std. Benzie Co. mon. in	3/8" pipe w/plastic cap
Power Pole S87°E 61.33	monument box	15" Cedar N80°E 101.05
8" Hemlock N30°W 121.9	Power Pole N53°E 39.85	Power Pole S35°E 121.00
12" Ash N83°W 74.60	Tel. Pole S57°E 65.05	Set ced. post w/loc. tag
1/2" pipe Due W 40.85	12" W. Pine S43°W 99.0	S89°E 40.0
SE Sec. 35 "T" iron	on center E-W & N-S Co. rds.	Ctr. US-31 Due W 1'
Due W 9.54		Conc. ROW mon. S38°E 112.3

SIGNED BY Carl F. Roser 8-20-75 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SOUTH PART OF Benzie
 BENZONIA TOWNSHIP County