

**SURVEY &  
REMONUMENTATION**

MAY 05 1997

LIBER 2 PAGE 51

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
BENZIE COUNTY  
RECORDED

For corners in

<u>Benzie</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>25N</u> R <u>15W</u>	<u>E-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1/22/1997 1:55:05 PM  
MICHELLE R. GRAY  
REGISTER OF DEEDS  
# PAGES \_\_\_\_\_

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John B. Smendzuik, in a field survey on 11/4/95 and 11/22/96, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**E-11: G.L.O. set post and witnesses - 10" Lynn N74°W 12.54' and 8" Lynn S79°E 21.78'. 1969-1970 B.C.R.C. reconstructed road and set 3/4" pipe x 12" long at intersection of Joyfield and Swamp Roads. Subsequent surveys by Bruce Jenema and Max Harris use iron as section corner.**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**E-11: Peer Group recommended and approved the position of the 3/4" pipe as best evidence of original G.L.O. position for corner. This is due to fact that iron best fits existing occupation and surveys.**

Ratified by Peer Group  
In accordance with P.A. 345  
Chairman [Signature]  
Date 12/21/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**E-11: Replaced 3/4" x 12" pipe with 3" diameter Benzie County Remonumentation Program concrete monument in a monument box in road intersection.**

- 18" Willow S08°E 142.43'
- Stop sign S19°E 49.46'
- Fiber optic riser S76°W 99.18'
- 6" Ash N50°W 65.76'

Signed by [Signature] Date 1/21/97

Surveyor's Michigan License No. 30895